

Fuel Station Canopy Demolition and UST Removal

The O6ENV crew saw cut and removed the concrete above the Underground Storage Tanks. All excavated materials were loaded, transported and disposed facility. The tank contents were removed via vacuum truck and disposed as well.



The (2) 15,000-gallon double-wall fiberglass tanks along with the associated fuel lines, pump islands, canopy and fuel dispensers were removed, cleaned, dismantled and loaded into containers. Following the tank removal, O6ENV assisted with the collection of soil samples for regulatory closure approval.

Following the completion of the entire site structure removal, rock backfill was placed and compacted in preparation for concrete replacement to restore the entire site.



[Contact us today to learn more!](#)